



REQUEST FOR PROPOSAL: Interior Renovation of Office Space on the third floor at SRHD	
NUMBER: 2020-0300	SUBMITTAL DATE: October 9, 2020 1:00pm (Pacific Time)
DIVISION: Administration	CONTACT PERSON: Carey Weiler 509.323.2855

Addendum 2020-0300.1

INTRODUCTION

The following information is provided to the potential Bidders for the above names RFP and shall become a part thereof. No consideration will be allowed due to any potential Bidder not being aware of or familiar with this addendum.

ACKNOWLEDGEMENT OF RECEIPT

The bidder must acknowledge receipt of this addendum on its Proposal for its Proposal to be deemed acceptable. This addendum shall form part of the RFP solicitation and is to be read, interpreted, and coordinated with all other parts. The following revisions supersede the information in the original instructions and specifications issues for the above name project.

PURPOSE

The purpose of this Addendum is to make the following change:

Attachment D: Deputy Director Conference Room and New Office

- a. For conference room we will be installing a monitor that will be provided by Spokane Regional Health District that will need electrical and data. Data will be provided by another company and will not be part of the RFP. The electrical will need to be placed on the following wall and will have the outlet hidden behind the wall mount.
- b. Light switch for the lights in the new conference room.
 - a. Originally it was stated in the RFP that the electrical switches would need to be moved from Patricia's area outside her office for easier access. We would now like to have the two lights that would be part of Patricia's office be on the switch outside of her office and the switch for the two lights in the new conference room be on a switch on the new wall as you walk into the conferenced room.
 - b. We will not have the lights for the conference room be all on one switch, they will still be on separate switches so that if the monitor is being used we have the opportunity to turn off the lights near the monitor and still have lights over the conference table.
 - c. All damaged or missing carpet will be replaced with carpet tile of Tandem Aftermath.

Attachment E: Quality, Planning and Assessment

- a. Office #2 – light switch from the demolished wall will need to be moved to an existing wall near the remaining door.
- b. Office #1 – light switches will need to be added to existing circuit.
- c. Office #3 – light switches will need to be added to existing circuit.
- d. All damaged or missing carpet will be replaced with carpet tile of Tandem Aftermath.